

engineering · planning · environmental · construction

701 Xenia Avenue South Suite 300 Minneapolis, MN 55416 Tel: 763-541-4800 Fax: 763-541-1700

September 1, 2015

Ms. Laura Jester and Ms. Karen Chandler Bassett Creek Watershed Commission 16145 Hillcrest Lane Eden Prairie, MN 55346

Re: Honeywell Enhancement/Improvement Project - 50% Submittal

Dear Ms. Jester and Ms. Chandler:

We are currently in the final design phase of the Honeywell Pond Enhancement/Improvement Project. The 50% plans are consistent with the proposed design in the feasibility report, which was approved at the October 16, 2014 Board meeting. Refer to **Table 1** for key design aspects between exiting condition, the feasibility report, and the proposed design along with explanations for any differences.

# 1. General Pond Design

The design of the Honeywell Pond is consistent with the improvements identified in the feasibility report. One slight change from the feasibility report to the 50% design is that the general design of the pond has more of an undulating edge then what was originally proposed. See the attached plan detail for more details. In addition, the existing XP-SWMM model was updated to reflect the proposed trunk storm sewer system and the outlet from Douglas Drive to Bassett Creek. A further comparison of the 50% design and the feasibility report are outlined in the table below.

Table 1: Pond Design							
	Feasibility Report		Final	Design			
	Existing Condition	Proposed Condition	Existing Condition	Proposed Condition			
NWL (Outlet Elevation) (ft)	876.4	876.4	876.4	876.4			
Pond Surface Area at NWL (ac)	1.5	2.4	1.5	2.4			
100 Year HWL (Atlas 14) (ft)	884.2	884.2	884.6*	884.6			
Peak Flow Rate to Bassett Creek (cfs)	103.5	102.9	85.7*	85.4			
Pond Surface Area at HWL (ac)	3.6	3.6	3.6	3.6			
Dead Pool Volume (ac-ft)	3.7	12.6	3.7	11.2			
Live Pool Volume (ac-ft)	22	25.8	22	29.5			
Honeywell Pond Drainage Area (ac)	725	785	702	768			
TP removed (lb/yr)	36.3	51.6	36.3	60.9			
Percent TP Removed (%)	17.3	23.4	17.3	24.1			
Buffer	NA	10 foot 10:1 buffer around entire pond	NA	10 foot 10:1 buffer around entire pond			
Undulating edge	slight	slight	slight	undulating			

Ms. Laura Jester and Ms. Karen Chandler August 19, 2015 Page 2

## 2. Low Flow Diversion Structure

The design of the low flow diversion structure in the 50% plan is consistent with the feasibility report. See the attached plan detail for further information on the low flow diversion structure and weir.

# 3. TP Removals (Expanding Pond and 48 inch Low Flow Diversion and 4 foot Weir)

The September 2014 version of the feasibility report had a 48 inch low flow diversion system **without** a weir. The September P8 model demonstrated that the pond would remove 23.4% TP (51.6 lb/yr). The October 2014 version of the feasibility report had a 48 inch low flow diversion system **with** a 4 foot weir. The October P8 model demonstrated that the pond would remove 24.5% TP (61.9 lb/yr). The feasibility report included the 51.6 lb/yr value not the 61.9 lb/yr value. The feasibility report should have shown a 24.5% TP (61.9 lb/yr) for the 48 inch low flow diversion system **with** a 4 foot weir.

# 4. Pumping for Irrigation of Sandburg Fields

A water balance was developed using available volume in Honeywell Pond (first 1.5 feet below the NWL) and irrigation demand at Sandburg Fields. The water balance assumes 1 inch of irrigation will occur per week over 17 acres of fields. This results in an irrigation demand of 462,000 gallons per week. Analysis completed using 50 years of rainfall runoff data shows the proposed irrigation system and infiltration system will only have 6.0 days/year that the pond's pump will not be able to meet the estimated irrigation demand (the first 1.5 feet below the NWL are used). This allows for the following:

- Volume available to be pumped for approximately 2.5 weeks without rain
  - O The drawdown from upstream storage basins following a rainfall event will extend the timeframe where volume is available for pumping
- The pumping volume will fully replenish (if down the full 1.5 feet) with a 0.35 inch rain event

Table 2: Irrigate Sandburg Learning Center Fields						
	Feasibility Report	Final Design*				
Pumping Below NWL (ft)	1.5	1.5				
Volume of Water available to pump (ac-ft)	3.37	3.37				
Acres of irrigation (ac)	14	17				
Volume of water needed to irrigate per season (ac-ft)	13.25-26.52	28.3				
TP removed (lb/yr)	5.77 - 11.54	12.3				
Seed mix to be used in the 1.5 foot pond bounce zone	Not Stated in Report	33-261				

<sup>\*</sup> Assumes 1 inch per week

# 5. Additional Stormwater Management with Douglas Drive

## **Pumping for Douglas Drive Infiltration (Not Part of Honeywell Project)**

90% plan submittal is anticipated to include the construction of an underground infiltration system at 1576 Douglas Drive N. It is currently proposed to pump water to the infiltration system from

<sup>\*</sup> The existing conditions XP-SWMM model was updated to better reflect the "actual conditions" from Douglas Drive to Bassett Creek. Two 42 inch links were added to the downstream end of link PQ29-MH127. The first link is 429 feet and placed at a 1.08 percent grade while the second link is 884 feet and placed at a 0.75 percent grade. Data for these two links was gathered from record drawings of the system from Douglas Drive to Bassett Creek. The model used in the feasibility did not contain this update.

Honeywell Pond. The infiltration system is proposed to be located (at 1576 Douglas Drive N) where a house was recently removed as part of the project's right-of-way acquisition. There are three main reasons for this change. This is feasible for the following reasons:

- The water balance calculations for Honeywell Pond shows the volume of water available to be pumped is more than adequate for both irrigating the Sandburg Fields and for the Douglas Drive Infiltration System.
- CenterPoint Energy is abandoning a conduit under the rail road tracks. This conduit can be used to house the force main under the tracks avoiding the need for drilling under the tracks.
- Using water from Honeywell Pond will utilize pretreated stormwater which will extend the life of the infiltration system and reduce maintenance time and cost.

Table 3: Pump to Douglas Dr Infiltration System						
	Feasibility Report	Final Design				
Size of the Douglas Drive infiltration system (ac)	0.195	0.11				
Storage volume of the Douglas Drive infiltration system (ac-ft)	Not Stated in Report	0.1				
Assumed infiltration rate of Douglas Drive Infiltration System (in/hr)	0.4	0.4				
Volume of water infiltrated at Douglas Drive Infiltration System per season (ac-ft)	Not Stated in Report	5-9				
TP removed (lb/yr)	2.04 - 4.08	2-4				

As outlined in this memo, we feel the 50% plan is fully consistent with the design expectations in the feasibility report. If you have any questions or concerns feel free to contact me at 763-287-7188 or at <a href="mailto:pwillenbring@wsbeng.com">pwillenbring@wsbeng.com</a>.

Sincerely,


WSB & Associates, Inc.


Pete Willenbring, PE

Water Resources Vice President

## Attachments


- 50% Plan (0701Honeywell.pdf)
- Existing Conditions XP-SWMM model (Decola\_UTM\_Stor\_Closed\_EC\_FINAL\_Ex100114.xp)
- Proposed Conditions XP-SWMM model (Decola\_UTM\_Stor\_Closed\_EC\_FINAL\_Ex100114\_ForFinalDesign\_072815.xp)
- Existing Conditions P8 model (UpstreamEastWestwood rev08142014 Existing.p8c)
- Proposed Conditions P8 model (UpstreamEastWestwood\_rev073015\_\_Proposed Pond Expansion +low flow 48in with weir\_FINAL.p8c)






INFRASTRUCTURE | ENGINEERING | PLANNING | CONSTRUCTION


S.A.P. 128-020-016,ETC./CITY PROJECT NO. 10-04 SHEETS




WSB & Associates, Inc. 763-541-4800 - Fax 763-541-1700
INFRASTRUCTURE | ENGINEERING | PLANNING | CONSTRUCTION



FORCEMAIN PLAN S.A.P. 128-020-016,ETC./CITY PROJECT NO. 10-04 SHEETS





NOTE: SEE DRAINAGE PLANS FOR PIPE PROFILES


# STORM SEWER DIVERSION STRUCTURE **DESIGN SPECIAL 3**

NOT TO SCALE

85	NO.	DATE	BY	СНК	REVISIONS	Design By:	I HE
ed:						AJP Plan By:	MY D THE
÷ 8						ACJ	
Prir						Checked By: DRS	CERT
- L-						Approved By:	- CENT
Jate VSB /						AJP	DAT








GOLDEN	VALLEY,	MINNESOTA
--------	---------	-----------


SHEET

DRD1

OF

220





SECTION A-A

## TABLE

	C.B. OR M.H. DIA.	COVER DIAMETER	WEIGHT OF SECTION	Т	К	L	BOTTOM BARS EACH WAY
1)	48''	58''	1140 LBS.	6''	6''	8''	NO.5 AT 6"
_	54''	65''	1990 LBS.	8''	6''	8''	NO.5 AT 8"
	60''	72''	2510 LBS.	8''	7''	9''	NO.5 AT 7"
	66''	79''	3090 LBS.	8''	7''	9"	NO.5 AT 7"
	72''	86''	3720 LBS.	8''	8''	10''	NO.5 AT 6"
	78''	93''	4400 LBS.	8''	8''	10''	NO.5 AT 5"
	84''	100''	5140 LBS.	8''	9''	11''	NO.5 AT 5"
	90''	107''	5930 LBS.	8''	9"	11''	NO.5 AT 5"
	96''	114''	6770 LBS.	8''	9''	11''	NO.6 AT 6"
	102''	121''	7670 LBS.	8''	9''	12''	NO.6 AT 5"
	108''	126''	12520 LBS.	12"	10''	12''	NO.5 AT 6"
	120''	140''	15560 LBS.	12''	11''	13''	NO.5 AT 6"

(1) ONLY NECESSARY TO USE BOTTOM LAYER OF STEEL.

## NOTES:

AASHTO HS 25 LOADING.

MAXIMUM FILL HEIGHT 15 FT.

THE NO. 4020 SHALL BE PERMANENTLY MARKED ON THE TOP OF THE COVER.

EQUIVALENT STEEL AREAS IN WIRE MESH MAY BE USED.

REINFORCEMENT PER SPEC. 3301. GRADE 60. ANY STEEL REINFORCEMENT THAT IS WELDED DURING FABRICATION SHALL MEET THE REQUIREMENTS OF ASTM A706.

REFER TO PLANS FOR STEP REQUIREMENTS, HEIGHT, & DIAMETER. SEE SHEET (2 OF 2) FOR INSTALLATION DETAILS.

DESIGNER NOTE:

WHEN STRUCTURE IS USED AS A CATCH BASIN, GIVE X & Y COORDINATES OF BOTH THE CENTERLINE FOR A, C, F OR G STRUCTURE AND THE CENTERLINE FOR THE 4020 STRUCTURE.

DESIGNATION:

DESIGN DIA. - STANDARD PLATE EXAMPLE: DESIGN 66 - 4020

APPROVED NOV. 22, 2000

Delbert W. Gerdes

STATE DESIGN ENGINEER

STATE OF MINNESOTA DEPARTMENT OF TRANSPORTATION

MANHOLE OR CATCH BASIN FOR USE WITH OR WITHOUT TRAFFIC LOADS

STANDARD SPECIFICATION REFERENCE

REVISION DATE

3-22-2013 M.J.E.

NO. 4020J 1 OF 2

PLATE

STATE DESIGN ENGINEER

APPROVED <u>NOV. 22, 2000</u>

0 0

STATE OF MINNESOTA DEPARTMENT OF TRANSPORTATION


58" COVER DIAMETER

MANHOLE DIAMETER

SECTION A-A

MANHOLE OR CATCH BASIN FOR USE WITH OR WITHOUT TRAFFIC LOADS

STANDARD SPECIFICATION REFERENCE PLATE NO. 4020J REVISED 2 OF 2 10-29-2013 M.J.E.



## NOTES:

WHEN STRUCTURE IS USED AS A CATCH BASIN. GIVE X.Y COORDINATES OF BOTH THE CENTERLINE FOR A, C, F OR G STRUCTURE AND THE CENTERLINE FOR THE 4020 STRUCTURE.

SEE SHEET 1 OF 2 FOR HANDLING HOLE DETAILS AND ADDITIONAL INFORMATION.

- 1 PROVIDE A FULL MORTAR BED.
- ② WALL CONSTRUCTION MAY BE: CLASS II PRECAST PIPE STANDARD PLATE 3000 REINFORCED CONCRETE PIPE: CAST-IN-PLACE CONCRETE MEETING THE REQUIREMENTS OF CLASS II PIPE; OR MASONRY CONSTRUCTION (BRICK OR BLOCK), STANDARD PLATE 4000 - MANHOLE OR CATCH BASIN MASONRY.
- 3 PROVIDE MORTAR FILLETS TO FIT BOTTOM PORTIONS OF PIPE TO DIRECT FLOW TO OUTLET.