


PLYMOUTH CREEK STREAM RESTORATION PHASE 1

CITY PROJECT NO. WR250001


CITY OF PLYMOUTH, MINNESOTA



VICINITY MAP



Sheet List Table			
Rev #	Rev Date	Sheet Number	Sheet Title
GENERAL			
		G-001	COVER
CIVIL			
		C-001	CIVIL LEGEND
		C-002	GENERAL NOTES
		C-003	SWPPP
		C-004	SWPPP
		C-005	SWPPP
PROJECT LAYOUTS			
		C-101	GENERAL LAYOUT
		C-102	EXISTING CONDITIONS & EROSION CONTROL
		C-103	EXISTING CONDITIONS & EROSION CONTROL
		C-104	EXISTING CONDITIONS & EROSION CONTROL
DETAILS			
		C-201	DETAILS
		C-202	DETAILS
		C-203	DETAILS
		C-204	DETAILS
REMOVALS			
		C-301	REMOVALS
		C-302	REMOVALS
		C-303	REMOVALS
UNDERGROUND			
		C-401	PROPOSED CONDITIONS
		C-402	PROPOSED CONDITIONS
		C-403	PROPOSED CONDITIONS
		C-404	PROPOSED CONDITIONS
		C-405	PROPOSED CONDITIONS
SITE PLANS			
		C-601	VEGETATION ESTABLISHMENT PLAN
		C-602	VEGETATION ESTABLISHMENT PLAN
		C-603	VEGETATION ESTABLISHMENT PLAN



PROJECT No. 30495

PRELIMINARY

CIVIL LEGEND

<u>EXISTING</u>	
	BENCHMARK
	IRON MONUMENT FOUND
	EXISTING PROPERTY LINE
	EXISTING PLAT LOT LINE
	EXISTING RIGHT OF WAY LINE
	EXISTING EASEMENT LINE
	EXISTING PLAT EASEMENT LINE
	EXISTING GAS LINE MARKER
	EXISTING GAS GATE VALVE
	EXISTING POWER POLE
	EXISTING LIGHT POLE
	EXISTING LIGHT POLE W/SIGN
	EXISTING GUY WIRE
	EXISTING TRAFFIC SIGNAL ARM
	EXISTING SIGN
	EXISTING CULVERT W/FLARED END SECTION (F.E.S.)
	EXISTING FLARED END SECTION (F.E.S.)
	EXISTING CURB STOP
	EXISTING HYDRANT W/GATE VALVE
	EXISTING GATE VALVE
	EXISTING PROPANE TANK
	EXISTING SANITARY SEWER MANHOLE
	EXISTING SANITARY SEWER CLEANOUT
	EXISTING STORM SEWER CATCH BASIN
	EXISTING STORM SEWER MANHOLE
	EXISTING WATER MAIN
	EXISTING WATER SERVICE W/CURB STOP
	EXISTING SANITARY SEWER
	EXISTING SANITARY SEWER (RELIN W/ CIPP)
	EXISTING SANITARY FORCEMAIN
	EXISTING SANITARY SEWER SERVICE
	EXISTING STORM SEWER
	EXISTING STORM SEWER FORCEMAIN
	EXISTING STEAM PIPE
	EXISTING AIR CONDITIONER
	EXISTING UTILITY PEDESTAL
	EXISTING UTILITY MANHOLE
	EXISTING UTILITY VAULT
	EXISTING UNDERGROUND COMMUNICATIONS
	EXISTING UNDERGROUND FIBER
	EXISTING UNDERGROUND TELEPHONE
	EXISTING OVERHEAD TELEPHONE
	EXISTING UNDERGROUND TELEVISION
	EXISTING OVERHEAD TELEVISION
	EXISTING UNDERGROUND GAS
	EXISTING UNDERGROUND ELECTRIC
	EXISTING OVERHEAD POWER
	EXISTING BARBED WIRE FENCE
	EXISTING CHAIN LINK/STEEL FENCE
	EXISTING PVC/WOOD FENCE
	EXISTING RAILROAD
	EXISTING SHRUB
	EXISTING STUMP
	EXISTING BOULDER
	EXISTING TREE/TREE CLUSTER
	EXISTING SPRINKLER HEAD
	EXISTING CLUSTER BOX UNIT (CBU)
	EXISTING MAILBOX
	EXISTING CURB AND GUTTER

<u>PROPOSED</u>	
	NEW PROPERTY LINE
	NEW PLAT LOT LINE
	NEW RIGHT OF WAY LINE
	NEW EASEMENT LINE
	NEW PLAT EASEMENT LINE
	CONSTRUCTION EASEMENT
	CONSTRUCTION LIMITS
	NEW LIGHT POLE
	NEW LIGHT POLE W/SIGN
	NEW GUY WIRE
	NEW SIGN
	TRAFFIC CONTROL - DRUM
	TRAFFIC CONTROL - TUBULAR MARKER
	NEW CULVERT W/FLARED END SECTION (F.E.S.)
	NEW FLARED END SECTION (F.E.S.)
	NEW CURB STOP
	NEW HYDRANT W/GATE VALVE
	NEW GATE VALVE
	NEW TAPPING SLEEVE
	NEW FITTINGS
	NEW PLUG
	NEW SANITARY SEWER MANHOLE
	NEW SANITARY SEWER CLEANOUT
	NEW STORM SEWER CATCH BASIN
	NEW STORM SEWER MANHOLE
	NEW WATER MAIN
	NEW WATER MAIN (DIRECTIONAL DRILLED, CASD OR BURST)
	NEW WATER SERVICE W/CURB STOP (S.B. ELEV.)
	NEW SANITARY SEWER
	NEW SANITARY SEWER (DIRECTIONAL DRILLED OR CASD)
	NEW SANITARY FORCEMAIN
	NEW SANITARY SEWER SERVICE (S.S. ELEV.)
	NEW STORM SEWER
	NEW STORM SEWER (DIRECTIONAL DRILLED OR CASD)
	NEW STORM SEWER FORCEMAIN
	NEW STEAM PIPE
	INSULATION PER DETAIL
	NEW BARBED WIRE FENCE
	NEW CHAIN LINK/STEEL FENCE
	NEW PVC/WOOD FENCE
	NEW CLUSTER BOX UNIT (CBU)
	NEW MAILBOX
	NEW LARGE DECIDUOUS TREE
	NEW SMALL DECIDUOUS TREE
	NEW SHRUB
	NEW LARGE EVERGREEN TREE
	NEW SMALL EVERGREEN TREE

<u>REMOVALS</u>	
	INDICATES REMOVAL
	REMOVE CURB AND GUTTER
	REMOVE ASPHALT PAVEMENT
	REMOVE CONCRETE PAVEMENT
	REMOVE AGGREGATE SURFACE
	UNIFORM MILL & OVERLAY
	TAPERED MILL & OVERLAY
	LEVELING COURSE
	RECLAIM
	ASPHALT PATCH
	CHIP SEAL
	TREE REMOVAL

<u>PAVEMENT</u>	
	NEW INFLOW CURB AND GUTTER
	NEW OUTFLOW CURB AND GUTTER
	NEW ASPHALT SURFACE
	NEW CONCRETE SURFACE
	NEW GRANULAR SURFACE
	NEW CRUSHED CONCRETE SURFACE
	NEW DECORATIVE COLORED CONCRETE
	NEW ASPHALT SIDEWALK/MULTI-USE PATH
	NEW CONCRETE SIDEWALK/MULTI-USE PATH
	NEW CONCRETE APPROACH/DRIVEWAY
	NEW DETECTABLE WARNING PANEL
	NEW GRAVEL APPROACH/DRIVEWAY
	NEW CONCRETE VALLEY GUTTER
	NEW MEDIAN NOSE APRON
	NEW ADA RAMP W/WARNING PANEL

	DISTURBANCE AREA / TOPSOIL REMOVAL
	REMOVE STOCKPILE
	EXISTING STOCKPILE
	TEMPORARY STOCKPILE
	PERMANENT STOCKPILE
	REAR YARD GRADING
	GRASS BUFFER STRIP
	TOPSOIL, SEEDING & BLANKET

<u>MISCELLANEOUS</u>	
	EXISTING RIPRAP
	NEW RIPRAP
	EXISTING LANDSCAPING AREA
	NEW LANDSCAPING AREA
	EXISTING WATER SURFACE
	NEW WATER SURFACE
	EXISTING WETLAND

	DRAINAGE BREAK LINE
	EXISTING DRAINAGE DIRECTION
	FINISHED DRAINAGE DIRECTION & SLOPE
	FINISHED GRADE
	EXISTING CONTOUR ELEVATION
	FINISHED CONTOUR ELEVATION
	GRADE ELEVATIONS
	SEDIMENTATION CONTROL WATTLE
	SEDIMENTATION CONTROL FENCE
	ROCK CHECK
	STABILIZED CONSTRUCTION ENTRANCE
	CONCRETE WASHOUT
	INLET PROTECTION DEVICE

ABBREVIATIONS:

BOC = BACK OF CURB
 BOW = BACK OF WALK
 C = COMMUNICATION
 CB# = STORM SEWER CATCH BASIN
 CIPP = CURED IN PLACE PIPE
 CL = CENTERLINE
 CSP = CORRUGATED STEEL PIPE
 CO# = SANITARY SEWER CLEANOUT
 CS# = CONTROL STRUCTURE
 DIA = DIAMETER
 DIP = DUCTILE IRON PIPE
 E = ELECTRICAL
 ECC = EDGE OF CRUSHED CONCRETE
 EG = EXISTING GRADE
 EOC = EDGE OF CONCRETE
 EOG = EDGE OF GRAVEL
 EOP = EDGE OF PAVEMENT
 EOW = EDGE OF WALK
 EX = EXISTING
 F = FIBER OPTIC
 FES = FLARED END SECTION
 FG = FINISHED GRADE
 FL = FLOWLINE
 FM = FORCEMAIN
 G = GAS LINE
 HP = HIGH POINT
 INV = INVERT
 LP = LOW POINT
 MA = MATCH
 M# = STORM SEWER MANHOLE
 MT# = STORM SEWER TEE MANHOLE
 MM# = STORM SEWER MULTI-MANHOLE
 MC = MIDPOINT OF CURVE
 OHP = OVERHEAD POWER
 OHT = OVERHEAD TELEPHONE
 OHTV = OVERHEAD TELEVISION
 PC = POINT OF CURVATURE
 PRC = POINT OF REVERSE CURVE
 PVC = POLYVINYL CHLORIDE PIPE
 PT = POINT OF TANGENCY
 RIM = RIM OF STRUCTURE
 S# = SANITARY SEWER MANHOLE
 S.B. ELEV = STOP BOX ELEVATION
 S.S. ELEV = SANITARY SEWER SERVICE INVERT
 SS = SANITARY SEWER
 ST = STORM SEWER
 STA = ALIGNMENT STATION
 T = TELEPHONE
 TOC = TOP OF CONCRETE
 TOP = TOP OF PAVEMENT
 TOP = TOP OF PIPE
 TOW = TOP OF WALK
 TR# = SANITARY TELEVISION RISER
 TRANS = TRANSFORMER
 TV = TELEVISION
 U = UTILITY (UNKNOWN UTILITY)

PRELIMINARY



CIVIL
 PLYMOUTH CREEK STREAM RESTORATION PHASE 1
 CITY PROJECT NO. WR250001
 CITY OF PLYMOUTH, MINNESOTA
 CIVIL LEGEND

DATE:	12.02.2025
REV DATE:	---
REV NUM:	---
RECORD:	---
PROJECT No.	30495
MANAGER:	JCM
DESIGNER:	QDS
DRAFTER:	DWA
REVIEWER:	DTE

C-001

GENERAL NOTES:

1. Take necessary precautions required to protect adjacent properties during the construction operations.
2. Notify Engineer where section, subsection or property monuments are encountered, before such monuments are removed. Protect and carefully preserve all property markers and monuments until the engineer and authorized surveyor has witnessed or otherwise referenced the location.
3. Coordinate a staging area location with the City for construction. There is no guarantee that City has an area suitable for staging.
4. The removal and replacement of existing street signs are incidental to the installation of the new utility. Replace any damaged signs. Coordinate with homeowners or businesses on the removal/relocation of personal/business affects prior to construction taking place in that area.
5. All mailbox relocations must be coordinated with the city and the post office.
6. The drawings designate those existing items for removal, replacement, or improvement. If not designated for removal, replacement, or improvement, all other existing items within the site to be protected.
7. Any construction traffic damage to roads outside the construction area to be repaired by the contractor.

UNDERGROUND NOTES:

1. Coordinate any utility relocations.
2. Unless otherwise noted, any removal, relocation, replacement, or bracing of power poles or any other utilities is the responsibility of the Contractor.
3. Existing utilities (both public and private) shown on the plans are approximate and may not be complete. It will be the contractor's responsibility to verify and locate any utilities prior to excavation. There will be no additional payment for exploratory time.
4. There is a potential for water on the project. It shall be the contractor's responsibility to dewater for constructability.
5. No extra payment will be made for bedding material for pipe, structures, or fittings.
6. The subsurface utility information in this plan is Utility Quality Level D. This quality level was determined according to the

guidelines of ASCE 38-02 entitled "Standard Guidelines for the Collection and Depiction of Existing Subsurface Utility Data".

7. Not all fittings required for a complete installation may be shown on the plans. Provide all required fittings.

REMOVAL NOTES

1. All miscellaneous debris, fittings, pipe material, appurtenances etc. Resulting from construction operations shall be first right of refusal to the owner. Otherwise, it will become the property of the contractor and shall be properly disposed of off-site.
2. All removals shall be saw cut. Saw cuts must be full depth.

TRAFFIC CONTROL NOTES:

1. The contractor will be responsible for maintaining access to all businesses/residences/public facilities at all times. This would include building & maintaining any required temporary access roadways.
2. Contractor must follow the current M.U.T.C.D. for traffic control for any and all construction operations that interfere with traffic.
3. Contractor to give no less than 48 hour notice prior to any work being done on the project. All no parking signs and any traffic control shall be posted at least 48 hours prior to work commencing.

PRELIMINARY



CIVIL
 PLYMOUTH CREEK STREAM RESTORATION PHASE 1
 CITY PROJECT NO. WR250001
 CITY OF PLYMOUTH, MINNESOTA
GENERAL NOTES

DATE:	12.02.2025
REV DATE:	---
REV NUM:	---
RECORD:	---
PROJECT No.	30495
MANAGER:	JCM
DESIGNER:	QDS
DRAFTER:	DWA
REVIEWER:	DTE

C-002

Project Description/Location:

The project is located in the City of Plymouth in Hennepin County, MN. The project corridor consists of approximately 2,400 linear feet of Plymouth Creek between Dunkirk Lane North and Vicksburg Lane North, south of Old Rockford Road and north of County Road 9 (Rockford Road). The project proposes to install a number of bank and channel stabilization practices to improve channel conditions and enhance aquatic habitat. The project will also include a variety of vegetation improvements within the adjacent riparian areas, including removing invasive and undesirable species and planting native species.

Land Feature Changes:

Total disturbed area: 3.99 acres
 Total existing impervious area: 0.49 acres
 Total proposed impervious area: 0.49 acres
 Total proposed net change in impervious area: 0.00 acres

Project Contacts:

	Agency	Contact	Phone No.
Owner:	City of Plymouth	Ben Scharenbroich	(763) 509-5527
Contractor:	TBD	TBD	TBD
State:	MPCA	MPCA Duty Officer	(651) 649-5451

Chain of Responsibility:

The Contractor is the permittee for the national pollutant discharge elimination system (NPDES) construction permit. The contractor is responsible to comply with all aspects of the NPDES construction permit at all times until the notice of termination (NOT) has been filed with the MPCA. The contractor will develop a chain of command with all operators on the site to ensure that the SWPPP will be implemented and stay in effect until the construction project is complete, the entire site has undergone final stabilization, and a notice of termination (NOT) has been submitted to the MPCA.

Contractors Responsibilities:

The Contractor shall be responsible for compliance with, monitoring, and maintenance of the requirement of the MPCA general storm water permit for construction activity. The Contractor must identify a certified erosion and sediment control supervisor. This person must be knowledgeable and experienced in the application of erosion prevention and sediment control bmp's. This person is to oversee the implementation of this SWPPP, and the installation, inspection, and maintenance of the erosion prevention and sediment control bmp's before, during, and after construction. The SWPPP is to remain in effect until the project is complete, the entire site has undergone final stabilization, and the MPCA permit been terminated.

Project Personnel and Training:

Name of person with Best Management Practices (BMP) experience who will oversee SWPPP implementation and coordinate with contractor:
 TBD and will be documented in this SWPPP narrative prior to start of construction. (First name, last name, company)

SWPPP Designer:

Company: Moore Engineering Inc.
 Name: Kelsey Kline
 Email: Kelsey.kline@mooreengineeringinc.com
 Phone: 320-281-5493
 Training date(s): 5/1/2025
 Training activity/content: Design of Construction SWPPP, University of Minnesota

Individual overseeing implementation, revision and/or amendment of the SWPPP that are available for an onsite inspection within 72 hours upon request of MPCA:

TBD and will be documented in this SWPPP narrative prior to start of construction.

Company: []
 Name: []
 Email: []
 Phone: []
 Training date(s): []
 Training activity/content: []

Individual performing or supervising the installation, maintenance and repair of BMPs:

TBD and will be documented in this SWPPP narrative prior to start of construction.

Company: []
 Name: []
 Email: []
 Phone: []
 Training date(s): []
 Training activity/content: []

Discharges to special and impaired waters:

Discharging into a special or impaired water must comply with MNR100001 Permit 2023 reference 23 of the NPDES Permit. Plymouth Creek is impaired for aquatic life (Benthic macroinvertebrates bioassessments; Chloride) and aquatic recreation (E. coli) and Medicine Lake is impaired for

aquatic consumption (mercury), aquatic life (fish bioassessments), and aquatic recreation (nutrients). Both Plymouth Creek and Medicine Lake have established TMDL goals. Plymouth Creek (Basset Creek) is identified as an impaired waterbody and is included in the Upper Mississippi River Bacteria TMDL and Protection Plan and the Twin Cities Metro Area Chloride TMDL approved by the EPA. The creek also drains to Medicine Lake, which is impaired for excess nutrients and has an approved Medicine Lake Nutrient TMDL (PRJ06316-001). The project will improve water quality and habitat by repairing actively eroding sites by stabilizing streambanks; providing and improving instream and riparian habitats; and preventing erosion at other sites by installing preemptive measures to protect existing streambanks. Overall, this project will reduce erosion, total suspended solids, and phosphorous loading to Plymouth Creek and downstream waters.

Discharges to Wetlands:

Discharging into a wetland must comply with MNR100001 Permit 2023 reference 22 of the NPDES Permit. The projects will have impacts to wetlands, and a Section 404 Permit will be obtained prior to construction and will obtain WCA approval.

Permits:

The following water related permits apply to this project:

Agency	Type of Permit
Minnesota Pollution Control Agency (MPCA)	NPDES Construction Permit 401 Water Quality Certification
City of Plymouth	WCA Approval
Department of Natural Resources (DNR)	Public Waters Work
Amy Corps of Engineers	Section 404
Basset Creek Water Management Commission	Floodplain Review

Stormwater mitigation measures proposed to be part of the final project in any environmental review document, endangered species review, archeological or other required local, state, or federal review conducted for the project:

There are no stormwater mitigation measures required as a result of an environmental, archeological or agency review. All mitigation measures have been addressed in this plan set or the special provisions.

Any required site assessments for groundwater or soil contamination:

No site assessment for groundwater or soil contamination was conducted prior to construction for the project.

Estimated Quantities:

Item	Estimated Quantity
Flotation Silt Curtain	50 LF
Erosion Control Blanket Cat 20	2,775 SY
Vegetation Establishment	3.5 AC

SWPPP Amendments:

Permittee must amend SWPPP within 7 days to include additional requirements to correct problems identified or address the following situations:

1. There is a change in design, construction, operation, maintenance, weather or seasonal conditions.
2. Inspections or investigations by site owner or operators, USEPA or MPCA officials determine the SWPPP is not minimizing discharge of pollutants to surface waters or underground waters or discharges are causing water quality standard exceedances.
3. The SWPPP is not achieving the objectives of minimizing pollutants in stormwater discharges associated with construction activity, or the SWPPP is not consistent with the terms and conditions of the permit.
4. The MPCA determines that the project's stormwater discharges may cause, have reasonable potential to cause, or contribute to non-attainment of any applicable water quality standard, or the SWPPP does not incorporate the applicable requirements of the permit.

BMP Selection and Stormwater Management:

Permittees must select, install, and maintain the BMPs identified in this SWPPP and in the NPDES permit in an appropriate and functional manner and in accordance with relevant manufacturer specifications and accepted engineering practices to minimize the discharge of pollutants in stormwater from construction activities. If erosion control netting is being utilized for soil stabilization, the permittee is encouraged to use products that have been shown to minimize impacts on wildlife.

Erosion/Sediment Control Measures:

Erosion and sediment control measures must comply with MNR100001 Permit 2023 reference 8 and 9 of the NPDES Permit.

- A. Areas not to be disturbed must be properly marked before work begins.
- B. Must minimize the need for disturbance of portions of the project with steep slopes.
- C. Exposed soils (including stockpiles) must have erosion protection/cover initiated immediately and completed within 14 days (or 7 days per Section 23).
- D. For DNR Public Waters with "work in waters restrictions" during specified fish spawning time frames, stabilization must be completed for all exposed soil areas within 200 feet of the water's edge, and draining to the water, within 24 hours during the restriction period.
- E. The wetted perimeter of the last 200 linear feet of ditches must be stabilized within 24 hours of connecting to a surface water or property line.
- F. Temporary or permanent ditches or swales that are being used as a sediment containment system during construction must be stabilized within 24 hours after no longer being used as a sediment containment system.
- G. Pipe outlets must have energy dissipation within 24 hours of connecting to a surface water or permanent stormwater treatment system.
- H. Mulch, hydro mulch, tackifier, polyacrylamide, or similar erosion prevention practices cannot be used within the normal wetted perimeter of drainage ditches or swale sections with a continuous slope greater than 2%.

PRELIMINARY



CIVIL
 PLYMOUTH CREEK STREAM RESTORATION PHASE 1
 CITY PROJECT NO. WR250001
 CITY OF PLYMOUTH, MINNESOTA
 SWPPP

DATE:	12.02.2025
REV DATE:	---
REV NUM:	---
RECORD:	---
PROJECT No.	30495
MANAGER:	JCM
DESIGNER:	QDS
DRAFTER:	DWA
REVIEWER:	DTE

C-003

- I. Must not disturb more land than what can be effectively inspected and maintained.
- J. Sediment control practices must be established on downgradient perimeters and upgradient of any buffer zones.
- K. If downgradient sediment controls are overloaded, based on frequent failure or excessive maintenance requirements, install additional upgradient sediment control practices or redundant BMPs to eliminate the overloading.
- L. Sediment control practices must be established at the base of stockpiles on the downgradient perimeter prior to the initiation of stockpiling.
- M. Stockpiles must be located outside of natural buffers or surface waters, including stormwater conveyances (e.g., curb and gutter systems) unless there is a bypass.
- N. Permittees must install temporary sediment basins as required in Section 14 of the NPDES Permit.
- O. Inlet protection BMPs shall be placed at all storm sewer system inlets prior to any work in those areas until permanent cover on all areas that receive discharge from the inlet are established.
- P. Inlet protection may be removed for a particular inlet if a safety concern is identified, and it must be documented in this SWPPP.
- Q. Vehicle tracking BMPs must be established where vehicles are exiting the site to minimize street tracking. Sediment tracked onto a public street must be removed within 24 hours.
- R. Must re-install all sediment control practices adjusted or removed to accommodate short-term activities immediately after the short-term activity is completed or before the next precipitation event even if the short-term activity is not complete.
- S. Street sweeping must be used in addition to vehicle tracking BMPs if the vehicle tracking BMPs alone are not adequate to prevent sediment tracking.
- T. Topsoil must be preserved unless infeasible.
- U. Soil compaction must be minimized.
- V. Discharges from BMPs must be directed to vegetated areas, unless infeasible.
- W. 50-foot natural buffers must be preserved or (if maintaining buffer is infeasible) redundant sediment controls must be provided when a surface water is located within 50 feet of the project's earth disturbances and drains to the surface water.
- X. Any sediment control made of soil must be temporarily or permanently stabilized within 24 hours.

Dewatering:

Dewatering related to the construction activity must comply with MNR100001 Permit 2023 reference 10 of the NPDES Permit. Dewatering must not cause nuisance conditions in surface waters. Turbid or sediment-laden waters must be discharged to a sediment control designed to prevent discharges with visual turbidity. It is prohibited to use receiving waters as part of the treatment area. Visual inspection and photos must be taken every 24 hours of operation to ensure adequate treatment has been obtained and nuisance conditions will not result from the discharge. If nuisance conditions occur from the discharge, dewatering must cease immediately, and corrective actions must occur before dewatering is resumed. Discharge from dewatering must be protected from erosion and scouring by an acceptable energy dissipation method, such as rock riprap, or sandbags. If using filters with backwash water, backwash water must be hauled away for disposal, returned to the beginning of the treatment process, or incorporated into the site in a manner that does not erode into runoff.

Temporary dewatering activities may be required. Therefore, it is possible that a permit for the temporary appropriation of waters of the state, non-irrigation from MNDNR will be required for this project. The contractor is responsible for obtaining this permit prior to commencing dewatering activities.

Site Inspection and Maintenance:

Inspections must comply with MNR100001 Permit 2023 reference 11 of the NPDES Permit. A trained person (as identified in item 21.2.b. of the NPDES Permit) must inspect the entire construction site a minimum of once every seven days during active construction and within 24 hours after a rainfall event greater than 0.5 inches in 24 hours. Inspect and maintain all temporary and permanent stormwater treatment BMPs, and erosion prevention and sediment control BMPs until the site has undergone final stabilization and the NOT has been submitted. Inspect areas adjacent to the project, surface water including drainage ditches and conveyance systems for evidence of erosion and sediment deposition. Inspect construction site vehicle exit locations, streets, and curb and gutter systems within and adjacent to the project for evidence of sedimentation from erosion or tracked sediment from vehicles. Inspect infiltration areas for signs of sediment deposition and compaction.

Record all inspections and maintenance activities in writing within 24 hours of above stated rainfall. Submit inspection reports in a format that is acceptable to the project engineer. Include the following in the records of each inspection:

- A. Date and time of inspection.
- B. Name of person(s) conducting inspection.
- C. Accurate findings of inspections, including the specific location where corrective actions are needed.
- D. Corrective actions taken (including dates, times, and party completing maintenance activities).
- E. Date and amount of all rainfall events greater than 0.5 inch in 24 hours. Rainfall amounts must be obtained by a properly maintained rain gauge installed onsite, or by a weather station that is within one mile or by a weather reporting system.
- F. If any discharge is observed during the inspection, it must be recorded. Discharge should also be photographed and described.
- G. Any amendments to the SWPPP proposed as a result of the inspection must be documented as required in Section 6 within seven (7) calendar days.
- H. All photographs of dewatering activities and documentation of nuisance conditions as a result of dewatering

Maintenance requirements are as listed below:

- A. All nonfunctional BMPs must be repaired, replaced, or supplemented with functional BMPs by the end of the next business day after discovery, or as soon as field conditions allow.

- B. All deltas and sediment deposits must be removed from surface waters (including drainage ways, catch basins, and other drainage systems). Removal and stabilization must be completed within seven days of discovery. Contact all appropriate authorities prior to working in surface waters.
- C. Sediment on paved surfaces must be removed within one calendar day of discovery, or within a shorter time to avoid a safety hazard.
- D. Perimeter control devices must be repaired, replaced, or supplemented when nonfunctional or sediment reaches one-half the height of the device. Complete repairs by the end of the next business day following discovery.
- E. Temporary and permanent sediment basins must be drained, and sediment removed when the depth of sediment collected reaches one-half storage volume within 72 hours of discovery.
- F. Dewatering operations must be inspected and photographed at the beginning and at least once every 24 hours during operation.
- G. Repair or replace inlet protection devices within 24 hours of discovery when they become nonfunctional, or sediment reaches 1/2 the height and/or depth of the device.

Methods to minimize soil compaction and preserve topsoil:

The contractor is responsible for marking areas that are not to be disturbed on the site. These areas must be marked prior to any construction occurring with stakes, flags, signs, or other appropriate methods. The contractor is responsible for not allowing construction equipment and vehicles to enter these areas in order to minimize soil compaction. Whenever feasible, the contractor must preserve topsoil from the construction site.

Pollution Prevention Measures:

- A. Store all construction materials that have potential to leach pollutants, landscape materials, pesticides, fertilizers, and treatment chemicals under cover (e.g., plastic sheeting or temporary roofs) to minimize contact with stormwater.
- B. Store, collect and dispose solid waste in compliance with Minn. R. Ch. 7035.
- C. Limit vehicle and equipment washing to a defined area of the site. Contain runoff from the washing area to a temporary sediment basin or other effective control. Properly dispose of all waste generated by vehicles and equipment washing. Engine degreasing is not allowed on the site.
- D. Provide effective containment for all liquid and solid wastes generated by washout of concrete, stucco, paint, form release oils, curing compounds and other construction materials. Liquid and solid washout wastes must not contact the ground. The liquid and solid waste that is produced must be disposed of in compliance with the MPCA rules. A sign must be installed indicating the location of the washout facility.
- E. Portable toilets must be positioned so that they are secure and sanitary waste will be properly disposed of.
- F. Fuel and maintain vehicles in a designated contained area whenever feasible. Use drip pans or absorbents to prevent the discharge of spills or leaked chemicals. Provide a spill kit at each location that vehicles and equipment are fueled or maintained at. Spills must be reported and cleaned up immediately as required by Minn. Stat. 115.061.
- G. Store all hazardous materials and toxic waste (including but not limited to oil, diesel fuel, gasoline, hydraulic fluids, paint, petroleum-based products, wood preservatives, additives, curing compounds, and acids) in sealed containers with secondary containment. Storage and disposal of hazardous waste materials must be in compliance with Minn. R. ch. 7045

Permit Termination Conditions:

A Notice of Termination (NOT) can be submitted to the MPCA once the following guidelines are met:

- A. Permanent uniform perennial vegetative cover must be established at minimum 70% density of its expected final growth.
- B. The permanent stormwater treatment system is constructed, meets all requirements, and is operating as designed.
- C. All temporary synthetic erosion prevention and sediment control BMPs must be removed, and the surrounding area must be restored to as designed.
- D. Clean out sediment from conveyance systems and permanent stormwater treatment systems (return to design capacity).
- E. For residential construction only, permit coverage terminates on individual lots if the lot is sold to the homeowner, structures are finished, and permanent cover is established. If permanent cover is not established install temporary erosion protection and downgradient perimeter control and distribute the MPCA's Homeowner Fact Sheet.
- F. For construction on agricultural lands, the disturbed land must be returned to its preconstruction agricultural use.
- G. When submitting the NOT ground or aerial photographs must be included to show the requirements of Section 13.2 of the NPDES Permit have been met.

Stabilization Time Frames:

- A. Initiate stabilization immediately when construction has temporarily or permanently ceased on any portion of the site. Complete stabilization within the time frame listed. In many instances this will require stabilization to occur more than once during the course of the project.
- B. Stabilize wetted perimeter of ditch (i.e. where the ditch gets wet).
- C. Application of mulch, hydromulch, tackifier and polyarylamide are not acceptable stabilization methods in these areas.
- D. Stabilize all areas of the site prior to the onset of winter. Any work still being performed will be snow mulched, seeded, and blanketed within the time frames in the NPDES permit.
- E. Topsoil berms must be stabilized in order to be considered perimeter control BMPs. Use rapid stabilization method 2, 3, or 4 as directed by the engineer. The seed mix used in the rapid stabilization may be substituted as follows:
 - a. Single year construction between May 1- August 1, seed with seed mixture 21-111
 - b. Single year construction between August 1and October 31, seed with seed mixture 21-112
 - c. Multi-year construction 22-111
- F. Keep ditches and exposed soils in an even rough graded condition in order to be able to apply erosion control mulches, hydromulches and blankets.
- G. **Area** **Time Frame**

PRELIMINARY



CIVIL
 PLYMOUTH CREEK STREAM RESTORATION PHASE 1
 CITY PROJECT NO. WR250001
 CITY OF PLYMOUTH, MINNESOTA
 SWPPP

DATE:	12.02.2025
REV DATE:	---
REV NUM:	---
RECORD:	---
PROJECT No.	30495
MANAGER:	JCM
DESIGNER:	QDS
DRAFTER:	DWA
REVIEWER:	DTE

C-004

Last 200 lineal feet of drainage ditch or swale
Remaining portions of drainage ditch or swale

Pipe and culvert outlets
Exposed soils and stockpiles

Within 200 feet of a public water

Within 24 hours of connection to surface water or property edge
Initiate immediately when construction activity has permanently or temporarily ceased 7 days per Section 23 of the NPDES Permit
24 hours
Initiate immediately when construction activity has permanently or temporarily ceased 7 days per Section 23 of the NPDES Permit
24 hours

Permanent Stormwater Treatment Systems:

There are no permanent stormwater treatment systems needed for the proposed project. If there is a permanent stormwater treatment system needed later in the project the contractor must design and implement the permanent stormwater treatment systems to be compliant with MNR100001 Permit 2023 reference 15 of the NPDES Permit.

Infeasibility Documentation:

No infeasible documentation requirements are anticipated for the project.

Record Retention:

The SWPPP must be kept at the site during construction by the permittee who has operational control of that portion of the site. The SWPPP and associated records must be stored and maintained by an employee or representative of the Owner for 3 years after the submission of the NOT. Responsibility for overseeing the records will be transferred to another employee or representative should the current personnel become uninvolved with the project or Owner. These records must include the following:

1. The final SWPPP
2. Any other stormwater related permits required for the project
3. Records of all inspection and maintenance conducted during construction
4. All permanent operation and maintenance agreements that have been implemented, including all right-of-way, contracts, covenants and other binding requirements regarding perpetual maintenance
5. All required calculations for design of the temporary and permanent Stormwater Management Systems.

Permanent Cover:

Permanent cover is achieved when vegetative cover is established at minimum 70% density of its expected final growth. This can be done by using permanent seeding with mulch, erosion control blankets, riprap, gravel, concrete, bituminous, etc. The specific permanent cover types can be found in the plan sheets.


Construction Phasing:

Construction will generally work upstream to downstream starting at Dunkirk Lane. Construction will be phased to avoid having areas open that are not being actively worked on. Flotation silt curtain will be moved within the stream as construction moves downstream to ensure disturbed sediment within the stream is captured.

Chemical Treatment Systems:

Must use polymers, flocculants, or other sedimentation treatment chemicals in accordance with accepted engineering practices. Must be in compliance with MNR100001 Permit 2023 reference 9.18 of the NPDES Permit and Minn. R. 7090.

PRELIMINARY





CIVIL
PLYMOUTH CREEK STREAM RESTORATION PHASE 1
PROJECT NO. WR250001
CITY OF PLYMOUTH, MINNESOTA
SWPPP

DATE:	12.02.2025
REV DATE:	---
REV NUM:	---
RECORD:	---
PROJECT No.	30495
MANAGER:	JCM
DESIGNER:	QDS
DRAFTER:	DWA
REVIEWER:	DTE

C-005

FILE LOCATION: Q:\Projects\30000\30400\30495 Stream Restoration\Plymouth\CAD\C3D\Production\30495_ProjectLayouts.dwg



PRELIMINARY




PROJECT LAYOUTS
 PLYMOUTH CREEK STREAM RESTORATION PHASE 1
 CITY PROJECT NO. WR250001
 CITY OF PLYMOUTH, MINNESOTA
 GENERAL LAYOUT




DATE:	11.26.2025
REV DATE:	---
REV NUM:	---
RECORD:	---
PROJECT No.:	30495
MANAGER:	JCM
DESIGNER:	QDS
DRAFTER:	DWA
REVIEWER:	DTE

NOTES:
 1. SEE SHEET C-001 FOR ADDITIONAL NOTES.
 2. COORDINATE ACCESS WITH CITY. ANY SITE ACCESS POINT WILL REQUIRE A STABILIZED CONSTRUCTION ENTRANCE. CONSTRUCTION ENTRANCE MUST BE IN PLACE PRIOR TO ANY WORK BEYOND TREE REMOVALS. DISTURBED AREAS SHALL BE DECOMPACTED, DRESSED WITH A MINIMUM OF 6" OF ONSITE TOPSOIL, AND SEED.

C-101



PRELIMINARY




- NOTES:
1. CLEAR AND GRUB TREES ACCORDING TO TREE SCHEDULE PROVIDED IN THE PROJECT MANUAL. TREES LEFT IN PLACE SHALL BE PROTECTED FROM DAMAGE THROUGHOUT DURATION OF CONSTRUCTION.
 2. CLEAR AND GRUB INVASIVE SPECIES INCLUDING BUCKTHORN, REED CANARY GRASS, AND BURDOCK.
 3. CONTRACTOR RESPONSIBLE TO REMOVE AND CLEAR ANY DEADFALL, DEBRIS, OR OTHER BLOCKAGES WITHIN THE CHANNEL. THIS WORK WILL BE CONSIDERED INCIDENTAL TO OTHER REMOVAL ITEMS.
 4. CONTRACTOR TO CLEAR AND GRUB BRUSH WITHIN PROJECT LIMITS AS DIRECTED BY THE ENGINEER.
 5. DOUBLE ROW FLOATING SILT CURTAIN TO BE INSTALLED ON THE DOWNSTREAM END OF ANY SECTION ACTIVELY BEING WORKED ON. INSTALL CURTAIN UPSTREAM OF THE NEXT DOWNSTREAM CULVERT OR BRIDGE.




PROJECT LAYOUTS
 PLYMOUTH CREEK STREAM RESTORATION PHASE 1
 CITY PROJECT NO. WR250001
 CITY OF PLYMOUTH, MINNESOTA
 EXISTING CONDITIONS & EROSION CONTROL

DATE:	12.02.2025
REV DATE:	---
REV NUM:	---
RECORD:	---
PROJECT No.	30495
MANAGER:	JCM
DESIGNER:	QDS
DRAFTER:	DWA
REVIEWER:	DTE

C-102




PRELIMINARY




- NOTES:
1. CLEAR AND GRUB TREES ACCORDING TO TREE SCHEDULE PROVIDED IN THE PROJECT MANUAL. TREES LEFT IN PLACE SHALL BE PROTECTED FROM DAMAGE THROUGHOUT DURATION OF CONSTRUCTION.
 2. CLEAR AND GRUB INVASIVE SPECIES INCLUDING BUCKTHORN, REED CANARY GRASS, AND BURDOCK.
 3. CONTRACTOR RESPONSIBLE TO REMOVE AND CLEAR ANY DEADFALL, DEBRIS, OR OTHER BLOCKAGES WITHIN THE CHANNEL. THIS WORK WILL BE CONSIDERED INCIDENTAL TO OTHER REMOVAL ITEMS.
 4. CONTRACTOR TO CLEAR AND GRUB BRUSH WITHIN PROJECT LIMITS AS DIRECTED BY THE ENGINEER.
 5. DOUBLE ROW FLOATING SILT CURTAIN TO BE INSTALLED ON THE DOWNSTREAM END OF ANY SECTION ACTIVELY BEING WORKED ON. INSTALL CURTAIN UPSTREAM OF THE NEXT DOWNSTREAM CULVERT OR BRIDGE

PROJECT LAYOUTS
 PLYMOUTH CREEK STREAM RESTORATION PHASE 1
 CITY PROJECT NO. WR250001
 CITY OF PLYMOUTH, MINNESOTA
 EXISTING CONDITIONS & EROSION CONTROL

DATE:	12.02.2025
REV DATE:	---
REV NUM:	---
RECORD:	---
PROJECT No.	30495
MANAGER:	JCM
DESIGNER:	QDS
DRAFTER:	DWA
REVIEWER:	DTE



PRELIMINARY




PROJECT LAYOUTS
 PLYMOUTH CREEK STREAM RESTORATION PHASE 1
 CITY PROJECT NO. WR250001
 CITY OF PLYMOUTH, MINNESOTA
 EROSION CONTROL

- NOTES:
- CLEAR AND GRUB TREES ACCORDING TO TREE SCHEDULE PROVIDED IN THE PROJECT MANUAL. TREES LEFT IN PLACE SHALL BE PROTECTED FROM DAMAGE THROUGHOUT DURATION OF CONSTRUCTION.
 - CLEAR AND GRUB INVASIVE SPECIES INCLUDING BUCKTHORN, REED CANARY GRASS, AND BURDOCK. CONTRACTOR RESPONSIBLE TO REMOVE AND CLEAR ANY DEADFALL, DEBRIS, OR OTHER BLOCKAGES WITHIN THE CHANNEL. THIS WORK WILL BE CONSIDERED INCIDENTAL TO OTHER REMOVAL ITEMS.
 - CONTRACTOR TO CLEAR AND GRUB BRUSH WITHIN PROJECT LIMITS AS DIRECTED BY THE ENGINEER.
 - DOUBLE ROW FLOATING SILT CURTAIN TO BE INSTALLED ON THE DOWNSTREAM END OF ANY SECTION ACTIVELY BEING WORKED ON. INSTALL CURTAIN UPSTREAM OF THE NEXT DOWNSTREAM CULVERT OR BRIDGE.


DATE:	12.02.2025
REV DATE:	---
REV NUM:	---
RECORD:	---
PROJECT No.	30495
MANAGER:	JCM
DESIGNER:	QDS
DRAFTER:	DWA
REVIEWER:	DTE

PRELIMINARY




- NOTES:**
1. DOUBLE SILT CURTAINS SHOULD BE SPACED 10' APART
 2. CONSTRUCT IN ACCORDANCE WITH (NDDOT SECTION 262) (MNDOT SECTION 2573 AND 3887.)


FLOATING SILT CURTAIN
NO SCALE 06.26.25




SECTION A-A



PLAN VIEW




TYPE A - SIDEWALK AND CURB



TYPE B - NO SIDEWALK OR CURB

CONSTRUCTION ENTRANCE
NO SCALE 06.26.25



PLAN VIEW

- COIR TOE NOTES:**
1. PLACE COIR LOG
 2. OVERLAY BRANCHES
 3. COVER BRANCHES WITH SOIL
 4. COVER SOIL WITH COIR EROSION CONTROL BLANKET & MANILA ROPE - MINIMUM 3/8"
 5. DEAD STAKES MAY BE HARVESTED ON SITE 3' TO 5' O.C., MIN 3" BURY, APPROXIMATE 2"-6" DIAMETER
 6. SHRUB PLUGS 3' TO 4' O.C., MIN 2' BURY, MIN 12" ABOVE MATTRESS


COIR TOE WITH BRUSH MATTRESS
NO SCALE




DETAILS
PLYMOUTH CREEK STREAM RESTORATION PHASE 1
CITY PROJECT NO. WR250001
CITY OF PLYMOUTH, MINNESOTA
DETAILS

DATE:	12.02.2025
REV DATE:	---
REV NUM:	---
RECORD:	---
PROJECT No.	30495
MANAGER:	JCM
DESIGNER:	QDS
DRAFTER:	DWA
REVIEWER:	DTE




PRELIMINARY



- ARCH VANE NOTES:**
1. CLASS IV RIPRAP SHALL BE FIELD STONE, NO LIMESTONE ALLOWED.
 2. FINAL PLACEMENT OF ARCH VANE AND RIPRAP TO BE FIELD VERIFIED BY ENGINEER.
 3. ALL VANES EXTEND UPSTREAM INTO FLOW OF CREEK.
 4. EXCAVATED SEDIMENT TO BE PLACE UPSTREAM OF ARCH VANE TO PROMOTE VOID FILLING. DO NOT PLACE SEDIMENT ABOVE TOP OF VANE AND DO NOT EXTEND SEDIMENT PLACEMENT MORE THAN 1' UPSTREAM OF ARCH VANES.




ARCH VANE DETAIL (TYPICAL)
NO SCALE



ROCK ARCH RAPIDS - STA 1+11 TO 1+41
NO SCALE

- ROCK ARCH RAPIDS NOTES:**
1. WATER SHOULD POOL AND FLOW OVER THE STRUCTURE, NOT THROUGH IT. MIX ALL RIPRAP WITH A WELL-GRADED GRANULAR FILTER PER MNDOT 3601.2E TO CREATE A VOID-FREE STRUCTURE. GRADE AND INSTALL THE MIX TO RESIST WASHOUT FROM RIVER CURRENTS.



ROCK ARCH RAPIDS - STA 24+39 TO 25+27
NO SCALE


- ROCK ARCH RAPIDS NOTES:**
1. WATER SHOULD POOL AND FLOW OVER THE STRUCTURE, NOT THROUGH IT. MIX ALL RIPRAP WITH A WELL-GRADED GRANULAR FILTER PER MNDOT 3601.2E TO CREATE A VOID-FREE STRUCTURE. GRADE AND INSTALL THE MIX TO RESIST WASHOUT FROM RIVER CURRENTS.




DETAILS
PLYMOUTH CREEK STREAM RESTORATION PHASE 1
CITY PROJECT NO. WR250001
CITY OF PLYMOUTH, MINNESOTA
DETAILS

DATE:	12.02.2025
REV DATE:	---
REV NUM:	---
RECORD:	---
PROJECT No.	30495
MANAGER:	JCM
DESIGNER:	QDS
DRAFTER:	DWA
REVIEWER:	DTE

PRELIMINARY




GRADED BANKS TYPICAL CHANNEL SECTION
NO SCALE




NOTE:
PROVIDE FLOTATION SILT CURTAIN TO CONTAIN SOIL MATERIAL DURING BANK RESLOPING OPERATIONS. FLOTATION SILT CURTAIN SHALL BE MAINTAINED AND RELOCATED AS OPERATIONS OF BANK RESLOPING PROGRESS. FLOTATION SILT CURTAIN SHALL NOT BE RELOCATED UNTIL CURRENT SITE IS STABILIZED.

GRADED BANK
NO SCALE



VEGETATED RIPRAP TYPICAL CHANNEL SECTION
NO SCALE




CLASS II VEGETATED RIP RAP TOE DETAIL
NO SCALE




DETAILS
PLYMOUTH CREEK STREAM RESTORATION PHASE 1
CITY PROJECT NO. WR250001
CITY OF PLYMOUTH, MINNESOTA
DETAILS

DATE:	12.02.2025
REV DATE:	---
REV NUM:	---
RECORD:	---
PROJECT No.	30495
MANAGER:	JCM
DESIGNER:	QDS
DRAFTER:	DWA
REVIEWER:	DTE



TYPICAL CHANNEL SECTION
NO SCALE




TYPICAL CHANNEL SECTION STATION 20+50 TO 23+84
NO SCALE

PRELIMINARY






DETAILS
PLYMOUTH CREEK STREAM RESTORATION PHASE 1
CITY PROJECT NO. WR250001
CITY OF PLYMOUTH, MINNESOTA
DETAILS

DATE:	12.02.2025
REV DATE:	---
REV NUM:	---
RECORD:	---
PROJECT No.	30495
MANAGER:	JCM
DESIGNER:	QDS
DRAFTER:	DWA
REVIEWER:	DTE



PRELIMINARY





- NOTES:
1. CLEAR AND GRUB TREES ACCORDING TO TREE SCHEDULE PROVIDED IN THE PROJECT MANUAL. TREES LEFT IN PLACE SHALL BE PROTECTED FROM DAMAGE THROUGHOUT DURATION OF CONSTRUCTION.
 2. CLEAR AND GRUB INVASIVE SPECIES INCLUDING BUCKTHORN, REED CANARY GRASS, AND BURDOCK.
 3. CONTRACTOR RESPONSIBLE TO REMOVE AND CLEAR ANY DEADFALL, DEBRIS, OR OTHER BLOCKAGES WITHIN THE CHANNEL. THIS WORK WILL BE CONSIDERED INCIDENTAL TO OTHER REMOVAL ITEMS.
 4. CONTRACTOR TO CLEAR AND GRUB BRUSH WITHIN PROJECT LIMITS AS DIRECTED BY THE ENGINEER.
 5. DOUBLE ROW FLOATING SILT CURTAIN TO BE INSTALLED ON THE DOWNSTREAM END OF ANY SECTION ACTIVELY BEING WORKED ON. INSTALL CURTAIN UPSTREAM OF ANY CULVERT OR BRIDGE.


REMOVALS
 PLYMOUTH CREEK STREAM RESTORATION PHASE 1
 CITY PROJECT NO. WR250001
 CITY OF PLYMOUTH, MINNESOTA
 REMOVALS

DATE:	12.02.2025
REV DATE:	---
REV NUM:	---
RECORD:	---
PROJECT No.	30495
MANAGER:	JCM
DESIGNER:	QDS
DRAFTER:	DWA
REVIEWER:	DTE

C-301



PRELIMINARY



- NOTES:**
- CLEAR AND GRUB TREES ACCORDING TO TREE SCHEDULE PROVIDED IN THE PROJECT MANUAL. TREES LEFT IN PLACE SHALL BE PROTECTED FROM DAMAGE THROUGHOUT DURATION OF CONSTRUCTION.
 - CLEAR AND GRUB INVASIVE SPECIES INCLUDING BUCKTHORN, REED CANARY GRASS, AND BURDOCK.
 - CONTRACTOR RESPONSIBLE TO REMOVE AND CLEAR ANY DEADFALL, DEBRIS, OR OTHER BLOCKAGES WITHIN THE CHANNEL. THIS WORK WILL BE CONSIDERED INCIDENTAL TO OTHER REMOVAL ITEMS.
 - CONTRACTOR TO CLEAR AND GRUB BRUSH WITHIN PROJECT LIMITS AS DIRECTED BY THE ENGINEER.
 - DOUBLE ROW FLOATING SILT CURTAIN TO BE INSTALLED ON THE DOWNSTREAM END OF ANY SECTION ACTIVELY BEING WORKED ON. INSTALL CURTAIN UPSTREAM OF ANY CULVERT OR BRIDGE.

REMOVALS


PLYMOUTH CREEK STREAM RESTORATION PHASE 1

CITY PROJECT NO. WR250001


CITY OF PLYMOUTH, MINNESOTA

REMOVALS

DATE:	12.02.2025
REV DATE:	---
REV NUM:	---
RECORD:	---
PROJECT No.	30495
MANAGER:	JCM
DESIGNER:	QDS
DRAFTER:	DWA
REVIEWER:	DTE




PRELIMINARY



REMOVALS
PLYMOUTH CREEK STREAM RESTORATION PHASE 1
CITY PROJECT NO. WR250001
CITY OF PLYMOUTH, MINNESOTA
REMOVALS


- NOTES:
- CLEAR AND GRUB TREES ACCORDING TO TREE SCHEDULE PROVIDED IN THE PROJECT MANUAL. TREES LEFT IN PLACE SHALL BE PROTECTED FROM DAMAGE THROUGHOUT DURATION OF CONSTRUCTION.
 - CLEAR AND GRUB INVASIVE SPECIES INCLUDING BUCKTHORN, REED CANARY GRASS, AND BURDOCK.
 - CONTRACTOR RESPONSIBLE TO REMOVE AND CLEAR ANY DEADFALL, DEBRIS, OR OTHER BLOCKAGES WITHIN THE CHANNEL. THIS WORK WILL BE CONSIDERED INCIDENTAL TO OTHER REMOVAL ITEMS.
 - CONTRACTOR TO CLEAR AND GRUB BRUSH WITHIN PROJECT LIMITS AS DIRECTED BY THE ENGINEER.
 - DOUBLE ROW FLOATING SILT CURTAIN TO BE INSTALLED ON THE DOWNSTREAM END OF ANY SECTION ACTIVELY BEING WORKED ON. INSTALL CURTAIN UPSTREAM OF ANY CULVERT OR BRIDGE.

DATE:	12.02.2025
REV DATE:	---
REV NUM:	---
RECORD:	---
PROJECT No.	30495
MANAGER:	JCM
DESIGNER:	QDS
DRAFTER:	DWA
REVIEWER:	DTE



PRELIMINARY

- LEGEND**
- GRADED BANKS WITH EROSION CONTROL BLANKET (TYP.)
 - GRADED BANKS WITH VEGETATED RIP RAP (TYP.)
 - COIR TOE
 - COIR TOE WITH BRUSH MATRESS (TYP.)
 - ROCK ARCH RAPIDS (TYP.)
 - ARCH VANE (TYP.)
 - NO BANK WORK



NOTE: EXISTING CHANNEL PROFILE WILL REMAIN UNCHANGED. ALL BANK STABILIZATION MEASURES SHALL TIE INTO THE EXISTING TOE AND PROFILE ELEVATIONS. THE CHANNEL PROFILE WILL ONLY BE MODIFIED AT ROCK ARCH RAPIDS AND ARCH VANE LOCATIONS.

UNDERGROUND
 PLYMOUTH CREEK STREAM RESTORATION PHASE 1
 CITY PROJECT NO. WR250001
 CITY OF PLYMOUTH, MINNESOTA
 PROPOSED CONDITIONS

DATE:	12.02.2025
REV DATE:	---
REV NUM:	---
RECORD:	---
PROJECT No.	30495
MANAGER:	JCM
DESIGNER:	QDS
DRAFTER:	DWA
REVIEWER:	DTE


FILE LOCATION: Q:\Projects\30000\30400\30495 StreamRestoration\Plymouth\CAD\C3D\Production\30495_PP.dwg



PRELIMINARY



- LEGEND**
- GRADED BANKS WITH EROSION CONTROL BLANKET
 - GRADED BANKS WITH VEGETATED RIP RAP
 - x- COIR TOE
 - ++++ COIR TOE WITH BRUSH MATTRESS
 - ⊠ ROCK ARCH RAPIDS
 - ⊠ ARCH VANE




UNDERGROUND
PLYMOUTH CREEK STREAM RESTORATION PHASE 1
PROJECT NO. WR250001
CITY OF PLYMOUTH, MINNESOTA
PROPOSED CONDITIONS

DATE: 12.02.2025
REV DATE: ---
REV NUM: ---
RECORD: ---

PROJECT No. 30495
MANAGER: JCM
DESIGNER: QDS
DRAFTER: DWA
REVIEWER: DTE


C-404



PRELIMINARY




- LEGEND**
- GRADED BANKS WITH EROSION CONTROL BLANKET
 - GRADED BANKS WITH VEGETATED RIP RAP
 - COIR TOE
 - COIR TOE WITH BRUSH MATTRESS
 - ROCK ARCH RAPIDS
 - ARCH VANE






UNDERGROUND
PLYMOUTH CREEK STREAM RESTORATION PHASE 1
CITY PROJECT NO. WR250001
CITY OF PLYMOUTH, MINNESOTA
PROPOSED CONDITIONS

DATE:	12.02.2025
REV DATE:	---
REV NUM:	---
RECORD:	---
PROJECT No.	30495
MANAGER:	JCM
DESIGNER:	QDS
DRAFTER:	DWA
REVIEWER:	DTE

FILE LOCATION: Q:\Projects\30000\30400\30495 StreamRestoration\Plymouth\CAD\CSD\Production\30495_Site.dwg



PRELIMINARY




SITE PLANS
 PLYMOUTH CREEK STREAM RESTORATION PHASE 1
 CITY PROJECT NO. WR250001
 CITY OF PLYMOUTH, MINNESOTA
 VEGETATION ESTABLISHMENT PLAN




DATE:	12.02.2025
REV DATE:	---
REV NUM:	---
RECORD:	---
PROJECT No.	30495
MANAGER:	JCM
DESIGNER:	QDS
DRAFTER:	DWA
REVIEWER:	DTE

C-601

FILE LOCATION: Q:\Projects\30000\30495 StreamRestoration\Plymouth\CAD\C3D\Production\30495_Site.dwg




PRELIMINARY



SITE PLANS
 PLYMOUTH CREEK STREAM RESTORATION PHASE 1
 CITY PROJECT NO. WR250001
 CITY OF PLYMOUTH, MINNESOTA
 VEGETATION ESTABLISHMENT PLAN

DATE:	12.02.2025
REV DATE:	---
REV NUM:	---
RECORD:	---
PROJECT No.	30495
MANAGER:	JCM
DESIGNER:	QDS
DRAFTER:	DWA
REVIEWER:	DTE

C-602



PRELIMINARY



SITE PLANS
 PLYMOUTH CREEK STREAM RESTORATION PHASE 1
 CITY PROJECT NO. WR250001
 CITY OF PLYMOUTH, MINNESOTA
 VEGETATION ESTABLISHMENT PLAN

DATE:	12.02.2025
REV DATE:	---
REV NUM:	---
RECORD:	---
PROJECT No.	30495
MANAGER:	JCM
DESIGNER:	QDS
DRAFTER:	DWA
REVIEWER:	DTE

C-603